

## ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
<b>04 . Preliminary &amp; Misc. Work</b>					
<b>04-130</b>	Contruction of RCC boundary pillar: Triangular; 75cm height.				
10.	<u>Materials : Concrete</u>				
	10-040 Bricks : 1st Class ....	8.1880	No.	@ Tk. . . .per 1000 No.	Tk. ....
	10-100 Cement : Portland ...	9.8000	kg	@ Tk. . . .per kg	Tk. ....
	10-380 Sand, FM >= 1.5 ....	0.0140	cum	@ Tk. . . .per cum	Tk. ....
				<b>Sub Total</b>	Tk. ....
20.	<u>Materials : Misc.</u>				
	20-500 Polythene Sheet : (1.0 kg per 16.00 sqm)	0.8085	sqm	@ Tk. . . .per sqm	Tk. ....
				<b>Sub Total</b>	Tk. ....
30.	<u>Wood Work</u>				
	30-020 Bamboo, Barrack : 7.5m long, 60-80mm dia	0.1890	No.	@ Tk. . . .per 100 No.	Tk. .... (Used 8 times)
					Tk. .... (10 % Salvage)
	30-460 Wood, Seasoned & Sawn, Jam ...	0.0200	cum	@ Tk. . . .per cum	Tk. .... (Used 8 times)
					Tk. .... (10 % Salvage)
				<b>Sub Total</b>	Tk. ....
40.	<u>Metal Work</u>				
	40-310 Nails; 37mm to 125mm ...	0.2000	kg	@ Tk. . . .per kg	Tk. ....
				<b>Sub Total</b>	Tk. ....
80.	<u>Labour</u>				
	80-375 Labour, Unskilled ...	0.2020	day	@ Tk. . . .per day	Tk. ....
	80-375 (Labour, Unskilled ...)	0.0020	day	@ Tk. . . .per day	Tk. .... (Misc. Sundry)
	80-425 Mason ..	0.1455	day	@ Tk. . . .per day	Tk. ....
	80-430 Mason, Head ...	0.0270	day	@ Tk. . . .per day	Tk. ....
	80-435 Mason, Helper ...	0.1580	day	@ Tk. . . .per day	Tk. ....
				<b>Sub Total</b>	Tk. ....
				<b>Sum of Sub Total</b>	Tk. ....
				<b>Overhead &amp;</b>	2.5 Tk. ....
				<b>Item Total</b>	Tk. ....
				<b>Contractor's</b>	10 % Tk. ....
				<b>Total</b>	Tk. ....
				<b>VAT</b>	5.5 % Tk. ....
				<b>Item Grand Total</b>	Tk. ....