

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
52 . Dismantling and Repair Work					
52-340	Repair roof cracks (100mmx50mm) with lime concrete (2:2:7):.				
10.	<u>Materials : Concrete</u>				
	10-040 Bricks : 1st Class	0.7300	No.	@ Tk. . . .per 1000 No.	Tk.
	10-145 Surki : 1st class bricks	0.0007	cum	@ Tk. . . .per cum	Tk.
	10-205 Lime, Slaked	0.5220	kg	@ Tk. . . .per kg	Tk.
				Sub Total	Tk.
20.	<u>Materials : Misc.</u>				
	20-140 Beal Fruit (solution)	0.0018	kg	@ Tk. . . .per kg	Tk.
	20-320 Molasses	0.0033	kg	@ Tk. . . .per kg	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.0546	day	@ Tk. . . .per day	Tk.
	80-375 (Labour, Unskilled)	0.0013	day	@ Tk. . . .per day	Tk. (Misc. Sundry)
	80-425 Mason	0.0109	day	@ Tk. . . .per day	Tk.
	80-430 Mason, Head	0.0013	day	@ Tk. . . .per day	Tk.
	80-435 Mason, Helper	0.0109	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.