

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
64. Building Construction					
64-430	12mm thick plain partex board ceiling in wooden frame				
30.	<u>Wood Work</u>				
	30-105 Board, Partex : 12mm thick.	1.0000	sqm	@ Tk. . . .per	sqm Tk.
	30-445 Wood, Seasoned & Sawn, Garjan	0.0132	cum	@ Tk. . . .per	cum Tk.
				Sub Total	Tk.
40.	<u>Metal Work</u>				
	40-595 Screw, 50mm.	1.5000	dzn	@ Tk. . . .per	dzn Tk.
	40-610 Rowel plug.	0.3333	dzn	@ Tk. . . .per	dzn Tk.
	40-755 Wire, G.I, 12 BWG	0.1104	kg	@ Tk. . . .per	kg Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-080 Carpenter	0.2000	day	@ Tk. . . .per	day Tk.
	80-085 Carpenter, Head	0.0500	day	@ Tk. . . .per	day Tk.
	80-090 Carpenter, Helper	0.2500	day	@ Tk. . . .per	day Tk.
	80-090 (Carpenter, Helper)	0.0010	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
	80-375 Labour, Unskilled	0.3300	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.