

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
80 . Plumbing Work					
80-260-20	Fixing G.I. water distribution pipe : 50mm dia				
50.	<u>Plumbing Work</u>				
50-034	Bend, G.I., 50mm dia	0.0223	No.	@ Tk. . . .per	No. Tk.
50-226	Elbow, G.I., 50mm dia	0.0333	No.	@ Tk. . . .per	No. Tk.
50-293	Jam Nut, G.I., 50mm dia	0.0050	No.	@ Tk. . . .per	No. Tk.
50-411	Pipe, G.I., 50mm dia	1.0000	m	@ Tk. . . .per	m Tk.
50-497	Socket, G.I., 50mm dia	0.1667	No.	@ Tk. . . .per	No. Tk.
50-544	Socket, Reducing, G.I., 75mm x 50mm	0.0031	No.	@ Tk. . . .per	No. Tk.
50-648	Tee, G.I., 50mm x 50mm	0.0167	No.	@ Tk. . . .per	No. Tk.
50-816	Union, G.I., 50mm dia	0.0100	No.	@ Tk. . . .per	No. Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
80-375	Labour, Unskilled	0.1353	day	@ Tk. . . .per	day Tk.
80-375	(Labour, Unskilled)	0.0014	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
80-560	Plumber	0.1312	day	@ Tk. . . .per	day Tk.
80-570	Plumber, Helper	0.1312	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.