

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
80 . Plumbing Work					
80-590	Taking out flushing cistern and refitting :.....				
20.	<u>Materials : Misc.</u>				
	20-415 Paint : Plastic Emulsion	0.2520	ltr	@ Tk. . . .per	ltr Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 (Labour, Unskilled)	0.0005	day	@ Tk. . . .per	day Tk. (Misc. Sundry)
	80-540 Painter/ Varnisher	0.2500	day	@ Tk. . . .per	day Tk.
	80-560 Plumber	0.5000	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.