

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-250-50	Brick work (1:4) in brick block : 50cmx50cmx15cm				
10.	<u>Materials : Concrete</u>				
	10-040 Bricks : 1st Class	15.9885	No.	@ Tk. . . .per 1000 No.	Tk.
	10-100 Cement : Portland ...	3.7500	kg	@ Tk. . . .per kg	Tk.
	10-380 Sand, FM >= 1.5	0.0107	cum	@ Tk. . . .per cum	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.0288	day	@ Tk. . . .per day	Tk.
	80-425 Mason	0.0271	day	@ Tk. . . .per day	Tk.
	80-430 Mason, Head	0.0008	day	@ Tk. . . .per day	Tk.
	80-435 Mason, Helper	0.0132	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & 2.5	Tk.
				Item Total	Tk.
				Contractor's 10 %	Tk.
				Total	Tk.
				VAT 5.5 %	Tk.
				Item Grand Total	Tk.