

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
52 . Dismantling and Repair Work					
52-290	Repairing of cracks with sand and cement (1:4):				
10.	<u>Materials : Concrete</u>				
	10-100 Cement : Portland	0.0088	kg	@ Tk. . . .per	kg Tk.
	10-370 Sand, FM >= 1.0	0.0001	cum	@ Tk. . . .per	cum Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-375 Labour, Unskilled	0.0015	day	@ Tk. . . .per	day Tk.
	80-425 Mason	0.0010	day	@ Tk. . . .per	day Tk.
	80-430 Mason, Head	0.0001	day	@ Tk. . . .per	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.