

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
64. Building Construction					
64-660	Supply, fitting, fixing of fixed glazed frame				
10.	<u>Materials : Concrete</u>				
	10-040 Bricks : 1st Class	2.4000	No.	@ Tk. . . .per 1000 No.	Tk.
	10-100 Cement : Portland ...	2.7500	kg	@ Tk. . . .per kg	Tk.
	10-380 Sand, FM >= 1.5 ...	0.0038	cum	@ Tk. . . .per cum	Tk.
				Sub Total	Tk.
20.	<u>Materials : Misc.</u>				
	20-250 Glass Panes : 3mm thick ...	1.0000	sqm	@ Tk. . . .per sqm	Tk.
	20-420 Paint : Red Oxide ...	0.2268	kg	@ Tk. . . .per kg	Tk.
	20-505 Putty ...	0.8577	kg	@ Tk. . . .per kg	Tk.
				Sub Total	Tk.
40.	<u>Metal Work</u>				
	40-030 Bar, Flat, M.S.	5.8360	kg	@ Tk. . . .per kg	Tk.
	40-040 Bar; Tee, M.S.	6.0000	kg	@ Tk. . . .per kg	Tk.
	40-105 Clamp Bar ...	2.5830	kg	@ Tk. . . .per kg	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-090 Carpenter, Helper ...	1.1788	day	@ Tk. . . .per day	Tk.
	80-090 (Carpenter, Helper ...)	0.0117	day	@ Tk. . . .per day	Tk. (Misc. Sundry)
	80-375 Labour, Unskilled ...	0.0960	day	@ Tk. . . .per day	Tk.
	80-425 Mason ..	0.0060	day	@ Tk. . . .per day	Tk.
	80-435 Mason, Helper ...	0.0030	day	@ Tk. . . .per day	Tk.
	80-445 Mechanic ...	2.3250	day	@ Tk. . . .per day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & 2.5	Tk.
				Item Total	Tk.
				Contractor's 10 %	Tk.
				Total	Tk.
				VAT 5.5 %	Tk.
				Item Grand Total	Tk.