

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
84. Electrical Work					
84-760	Installation of over-head L.T. distribution line				
60.	<u>Electrical Work</u>				
	60-010 Aluminium conductor;7/4.39mm dia	1.0000	m	@ Tk. . . .per m	Tk.
				Sub Total	Tk.
80.	<u>Labour</u>				
	80-205 Line man	0.0030	day	@ Tk. . . .per day	Tk.
	80-225 Foreman	0.0015	day	@ Tk. . . .per day	Tk.
	80-370 Labour, Skilled	0.0055	day	@ Tk. . . .per day	Tk.
	80-375 Labour, Unskilled	0.0095	day	@ Tk. . . .per day	Tk.
	80-375 (Labour, Unskilled)	0.0010	day	@ Tk. . . .per day	Tk. (Misc. Sundry)
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead &	2.5 Tk.
				Item Total	Tk.
				Contractor's	10 % Tk.
				Total	Tk.
				VAT	5.5 % Tk.
				Item Grand Total	Tk.