

তত্ত্বাবধায়ক প্রকৌশলীর দপ্তর
ডিজাইন সার্কেল-২, বাপাউবো
৭২ গ্রীণ রোড (৩য় তলা)
ঢাকা-১২১৫
ফোন - ৯১১৭৬০৯



Office of the
Superintending Engineer
Design Circle-II, BWDB
72 Green Road, Dhaka-1215
Telephone: 9117609
Email: design2_bwdb@yahoo.com

স্মারক নং-ক-৩২/আপডেট/১৯/২৩৮

তারিখঃ- ১৩/০৩/২০১৯ খ্রিঃ

বরাবর,
প্রধান প্রকৌশলী
ডিজাইন, বাপাউবো, ঢাকা।

বিষয়ঃ- Emergency কাজের জন্য দুইটি নতুন আইটেম ৪০-৪৯৫ ও ৪০-৪৯৬ BWDB Standard Schedule of Rates এ সংযোজন এবং পুরাতন আইটেম ৪০-৪৮৯ ও ৪০-৪৯৩- এর Analysis template সংশোধন প্রসঙ্গে।

মহোদয়,

যথাযথ সম্মান প্রদর্শন পূর্বক উপরোক্ত বিষয়ের প্রেক্ষিতে জানানো যাচ্ছে যে Emergency কাজের দুইটি নতুন আইটেম ৪০-৪৯৫ ও ৪০-৪৯৬ BWDB Standard Schedule of Rates এ সংযোজন করা হয়েছে এবং পুরাতন আইটেম ৪০-৪৮৯ ও ৪০-৪৯৩ এর Analysis template সংশোধন করা হয়েছে। আইটেম সমূহের Item Description (সংযুক্তি-১) এবং Analysis Template (সংযুক্তি-২) সংযুক্ত করা হল। বাপাউবো এর বিভিন্ন সার্কেলের জন্য উক্ত আইটেম সমূহের দর সংশ্লিষ্ট সার্কেলের তত্ত্বাবধায়ক প্রকৌশলীর নিকট প্রেরিত অত্র চিঠির কপির সাথে সংযুক্ত করা হল (সংযুক্তি-৩)।

ইহা আপনার সদয় অবগতির জন্য প্রেরণ করা হল।

স্বঃ

(মোঃ হারুন উর রশিদ)
তত্ত্বাবধায়ক প্রকৌশলী,
ডিজাইন সার্কেল-২,
বাপাউবো, ঢাকা।
পরিচিতি নং- ৬২০৫০১০০৫

স্মারক নং-ক-৩২/আপডেট/১৯/২৩৮

তারিখঃ-১৩/০৩/২০১৯ খ্রিঃ

অনুলিপি সংযুক্তিসহ সদয় অবগতি/অবগতির জন্য প্রেরণ করা হলঃ-

১. চীফ মনিটরিং, বাপাউবো, ঢাকা।
২. প্রধান প্রকৌশলী, কেন্দ্রীয় অঞ্চল, বাপাউবো, ঢাকা।
৩. প্রধান প্রকৌশলী, উত্তরাঞ্চল, বাপাউবো, রংপুর।
৪. প্রধান প্রকৌশলী, দক্ষিণাঞ্চল, বাপাউবো, বরিশাল।
৫. প্রধান প্রকৌশলী, উত্তর-পূর্বাঞ্চল, বাপাউবো, কুমিল্লা।
৬. প্রধান প্রকৌশলী, দক্ষিণ-পূর্বাঞ্চল, বাপাউবো, চট্টগ্রাম।
৭. প্রধান প্রকৌশলী, উত্তর-পশ্চিমাঞ্চল, বাপাউবো, রাজশাহী।
৮. প্রধান প্রকৌশলী, দক্ষিণ-পশ্চিমাঞ্চল, বাপাউবো, খুলনা।
৯. প্রধান প্রকৌশলী, মধ্য-পশ্চিমাঞ্চল, বাপাউবো, ফরিদপুর।
১০. প্রধান প্রকৌশলী, পওর, বাপাউবো, ঢাকা।
১১. তত্ত্বাবধায়ক প্রকৌশলী, বরিশাল পওর সার্কেল, বাপাউবো, বরিশাল।
১২. তত্ত্বাবধায়ক প্রকৌশলী, ভোলা পওর সার্কেল, বাপাউবো, ভোলা।
১৩. তত্ত্বাবধায়ক প্রকৌশলী, বগুড়া পওর সার্কেল, বাপাউবো, বগুড়া।
১৪. তত্ত্বাবধায়ক প্রকৌশলী, চাঁদপুর পওর সার্কেল, বাপাউবো, চাঁদপুর।
১৫. তত্ত্বাবধায়ক প্রকৌশলী, চট্টগ্রাম পওর সার্কেল, বাপাউবো, চট্টগ্রাম।
১৬. তত্ত্বাবধায়ক প্রকৌশলী, কুমিল্লা পওর সার্কেল, বাপাউবো, কুমিল্লা।
১৭. তত্ত্বাবধায়ক প্রকৌশলী, ঢাকা পওর সার্কেল, বাপাউবো, ঢাকা।
১৮. তত্ত্বাবধায়ক প্রকৌশলী, ফরিদপুর পওর সার্কেল, বাপাউবো, ফরিদপুর।
১৯. তত্ত্বাবধায়ক প্রকৌশলী, ফেনী পওর সার্কেল, বাপাউবো, ফেনী।
২০. তত্ত্বাবধায়ক প্রকৌশলী, যশোর পওর সার্কেল, বাপাউবো, যশোর।
২১. তত্ত্বাবধায়ক প্রকৌশলী, খুলনা পওর সার্কেল, বাপাউবো, খুলনা।
২২. তত্ত্বাবধায়ক প্রকৌশলী, কুষ্টিয়া পওর সার্কেল, বাপাউবো, কুষ্টিয়া।
২৩. তত্ত্বাবধায়ক প্রকৌশলী, মৌলভীবাজার পওর সার্কেল, বাপাউবো, মৌলভীবাজার।
২৪. তত্ত্বাবধায়ক প্রকৌশলী, ময়মনসিংহ পওর সার্কেল, বাপাউবো, ময়মনসিংহ।

২৫. তত্ত্বাবধায়ক প্রকৌশলী, পাবনা পওর সার্কেল, বাপাউবো, পাবনা।
২৬. তত্ত্বাবধায়ক প্রকৌশলী, রাজশাহী পওর সার্কেল, বাপাউবো, রাজশাহী।
২৭. তত্ত্বাবধায়ক প্রকৌশলী, রংপুর পওর সার্কেল-১, বাপাউবো, রংপুর।
২৮. তত্ত্বাবধায়ক প্রকৌশলী, রংপুর পওর সার্কেল-২, বাপাউবো, রংপুর।
২৯. তত্ত্বাবধায়ক প্রকৌশলী, সিলেট পওর সার্কেল, বাপাউবো, সিলেট।
৩০. তত্ত্বাবধায়ক প্রকৌশলী, ঠাকুরগাঁও পওর সার্কেল, বাপাউবো, ঠাকুরগাঁও।
৩১. তত্ত্বাবধায়ক প্রকৌশলী, কক্সবাজার পানি উন্নয়ন সার্কেল, বাপাউবো, কক্সবাজার।
৩২. তত্ত্বাবধায়ক প্রকৌশলী, পটুয়াখালী পানি উন্নয়ন সার্কেল, বাপাউবো, পটুয়াখালী।
৩৩. তত্ত্বাবধায়ক প্রকৌশলী, ডিজাইন সার্কেল-১, বাপাউবো, ঢাকা।
৩৪. তত্ত্বাবধায়ক প্রকৌশলী, ডিজাইন সার্কেল-৩, বাপাউবো, ঢাকা।
৩৫. তত্ত্বাবধায়ক প্রকৌশলী, ডিজাইন সার্কেল-৪, বাপাউবো, ঢাকা।
৩৬. তত্ত্বাবধায়ক প্রকৌশলী, ডিজাইন সার্কেল-৫, বাপাউবো, ঢাকা।
৩৭. তত্ত্বাবধায়ক প্রকৌশলী, ডিজাইন সার্কেল-৬, বাপাউবো, ঢাকা।
৩৮. পরিচালক, পরিকল্পনা পরিদপ্তর-১, বাপাউবো, ঢাকা।
৩৯. পরিচালক, পরিকল্পনা পরিদপ্তর-২, বাপাউবো, ঢাকা।
৪০. পরিচালক, পরিকল্পনা পরিদপ্তর-৩, বাপাউবো, ঢাকা।
✓ ৪১. সিস্টেম এনালিস্ট, সেন্ট্রাল আই,সি,টি সেল, চীফ মনিটরিং এর দপ্তর, বাপাউবো, ঢাকা। বোর্ডের
ওয়েবসাইট(www.bwdb.gov.bd) প্রকাশের জন্য।
৪২. নথির কপি।




(মোঃ হারুন উর রশিদ)

তত্ত্বাবধায়ক প্রকৌশলী,

ডিজাইন সার্কেল-২,

বাপাউবো, ঢাকা।

পরিচিতি নং- ৬২০৫০১০০৫


13/03/2019

Printed: March 13, 2019

ITEM DEFINITION REPORT

Item Code	Item Description	Unit Meas.
40 . Protective Work		
40-489	[For emergency work] Filling and dumping of geo-textile bags of different sizes and capacity at project/work site, protecting the geotextile bags from any damage, filling with locally available sand free from silt and clay, sewing along one transverse (top) side after filling, staking in measurable/countable stakes, marking with synthetic enamel paint during counting, dumping from properly positioned and anchored flat top engine boat over an area as per drawing including loading, unloading, sequential piling of geo-bags on the dumping edge of boat, cost of all materials & equipments and its mobilization, labour, incidental charges etc. complete as per technical specification, approved design and direction of Engineer in charge. [fill volume and weight will be measured after filling with dry sand]	no
40-489-10	. Geo-bag; inner size:1200mmx950mm, outer size:1250mmx1000mm, Fill Vol: 0.1664cum; wt: 250kg	no
40-489-15	. Geo-bag; inner size:1100mmx850mm, outer size:1150mmx900mm, Fill Vol: 0.1333cum; wt: 200kg	no
40-489-20	. Geo-bag; inner size:1075mmx850mm, outer size:1125mmx900mm, Fill Vol: 0.1164cum; wt: 175kg	no
40-489-30	. Geo-bag; inner size:950mmx750mm, outer size:1000mmx800mm, Fill Vol: 0.0840cum; wt: 125kg	no
40-489-40	. Geo-bag; inner size:900mmx700mm, outer size:950mmx750mm, Fill Vol: 0.0730cum; wt: 110kg	no
40-489-50	. Geo-bag; inner size:800mmx650mm, outer size:850mmx700mm, Fill Vol: 0.0520cum; wt: 80kg	no







ITEM DEFINITION REPORT

Item Code	Item Description	Unit Meas.
40 . Protective Work		
40-493	[For Emergency work] Supplying, filling and dumping of geo-textile bags of different sizes and capacity at project/work site, making with standard geo-textile fabric (Polyester fabric, Thickness$\geq$3.0 mm, mass$\geq$ 400gm/m²) and sewing in accordance with the drawing and Technical Specifications of BWDB and Schedule of Rates of BWDB, protecting the geotextile bags from any damage, filling with locally available sand free from silt and clay, sewing along one transverse (top) side after filling, staking in measurable/countable stakes, marking by synthetic enamel paint during counting, dumping from properly positioned and anchored flat top engine boat over an area as per drawing including loading, unloading, sequential piling of geo-bags on the dumping edge of boat, cost of all materials & equipments and its mobilization, labour, incidental charges etc. complete as per technical specification, approved design and direction of Engineer in charge. [fill volume and weight will be measured after filling with dry sand]	No.
40-493-10	. Geo-bag; inner size:1200mmx950mm, outer size:1250mmx1000mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.1664cum; wt: 250kg	No.
40-493-15	. Geo-bag; inner size:1100mmx850mm, outer size:1150mmx900mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.1333cum; wt: 200kg	No.
40-493-20	. Geo-bag; inner size:1075mmx850mm, outer size:1125mmx900mm geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.1164cum; wt: 175kg	No.
40-493-30	. Geo-bag; inner size:950mmx750mm, outer size:1000mmx800mm geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.0840cum; wt: 125kg	No.
40-493-40	. Geo-bag; inner size:900mmx700mm, outer size:950mmx750mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.0730cum; wt: 110kg	No.
40-493-50	. Geo-bag; inner size:800mmx650mm, outer size:850mmx700mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.0520cum; wt: 80kg	No.



ITEM DEFINITION REPORT

Item Code	Item Description	Unit Meas.
40 . Protective Work		
40-495	[For Emergency work] Filling and placing of geo-textile bags of different sizes and capacity at project/work site, protecting the geotextile bags from any damage, filling with locally available sand free from silt and clay, sewing along one transverse (top) side after filling sand, staking in measurable/countable stakes, marking with synthetic enamel paint during counting and placing in position as per drawing including levelling, dressing, preparation of base, cost of all materials & equipments and its mobilization, labour, incidental charges etc complete as per technical specification, approved design and direction of Engineer in charge. [fill volume and weight will be measured after filling with dry sand]	No.
40-495-10	. Geo-bag; inner size:1200mmx950mm, outer size:1250mmx1000mm, geo-fabric th.=>3.0mm, Fill Vol: 0.1664cum; wt: 250kg	No.
40-495-15	. Geo-bag; inner size:1100mmx850mm, outer size:1150mmx900mm, geo-fabric th.=>3.0mm, Fill Vol: 0.1333cum; wt: 200kg	No.
40-495-20	. Geo-bag; inner size:1075mmx850mm, outer size:1125mmx900mm geo-fabric th.=>3.0mm, Fill Vol: 0.1164cum; wt: 175kg	No.
40-495-30	. Geo-bag; inner size:950mmx750mm, outer size:1000mmx800mm geo-fabric th.=>3.0mm, Fill Vol: 0.0840cum; wt: 125kg	No.
40-495-40	. Geo-bag; inner size:900mmx700mm, outer size:950mmx750mm, geo-fabric th.=>3.0mm, Fill Vol: 0.0730cum; wt: 110kg	No.
40-495-50	. Geo-bag; inner size:800mmx650mm, outer size:850mmx700mm, geo-fabric th.=>3.0mm, Fill Vol: 0.0520cum; wt: 80kg	No.





ITEM DEFINITION REPORT

Item Code	Item Description	Unit Meas.
40 . Protective Work		
40-496	[For Emergency work] Supplying, filling and placing of geo-textile bags of different sizes and capacity at project/work site, making with standard geo-textile fabric (Polyester fabric, Thickness $\geq$ 3.0 mm, mass $\geq$ 400gm/m ²) and sewing in accordance with the drawing and Technical Specifications of BWDB and Schedule of Rates of BWDB, filling with locally available sand free from silt and clay, sewing along one transverse (top) side after filling, staking in measurable/countable stakes, marking by synthetic enamel paint during counting, placing in position as per approved drawing including levelling, dressing and preparation of base, cost of all materials & equipments and its mobilization, labour, incidental charges etc. complete as per technical specification, approved design and direction of Engineer in charge. [fill volume and weight will be measured after filling with dry sand]	No.
40-496-10	. Geo-bag; inner size:1200mmx950mm, outer size:1250mmx1000mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.1664cum; wt: 250kg	No.
40-496-15	. Geo-bag; inner size:1100mmx850mm, outer size:1150mmx900mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.1333cum; wt: 200kg	No.
40-496-20	. Geo-bag; inner size:1075mmx850mm, outer size:1125mmx900mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.1164cum; wt: 175kg	No.
40-496-30	. Geo-bag; inner size:950mmx750mm, outer size:1000mmx800mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.0840cum; wt: 125kg	No.
40-496-40	. Geo-bag; inner size:900mmx700mm, outer size:950mmx750mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.0730cum; wt: 110kg	No.
40-496-50	. Geo-bag; inner size:800mmx650mm, outer size:850mmx700mm, geo-fabric th. $\Rightarrow$ 3.0mm, Fill Vol: 0.0520cum; wt: 80kg	No.

11/2/19-2

Printed: March 13, 2019

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.166400	cum	@ Tk. . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.016640	cum	@ Tk. . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.011760	ltr	@ Tk. . . pe	ltr Tk.
	20-310 Lubricant (Mobilc oil etc.)	0.000390	ltr	@ Tk. . . pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	12.000000	m	@ Tk. . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001690	kg	@ Tk. . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.002350	No	@ Tk. . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.001475	day	@ Tk. . . pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000550	day	@ Tk. . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.002088	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000625	day	@ Tk. . . pe	day Tk.
	80-370 Labour, Skilled	0.075000	day	@ Tk. . . pe	day Tk.
	80-375 Labour, Unskilled	0.005000	day	@ Tk. . . pe	day Tk.
	80-477 Operator, Engine boat	0.001663	day	@ Tk. . . pe	day Tk.
	80-479 Helper (Engine boat)	0.001663	day	@ Tk. . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est 2.50%	Tk.
				Item Total	Tk.
				Contractor's Prof 10.00%	Tk.
				Total	Tk.
				VAT 7.00%	Tk.
				Item Grand Total	Tk.

(A)

BM

✓

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.133300	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.013330	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.009100	ltr	@ Tk. . . .pe	ltr Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000300	ltr	@ Tk. . . .pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	11.400000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001500	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.002100	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.001125	day	@ Tk. . . .pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000450	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.002013	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000625	day	@ Tk. . . .pe	day Tk.
	80-370 Labour, Skilled	0.068000	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.004550	day	@ Tk. . . .pe	day Tk.
	80-477 Operator, Engine boat	0.001338	day	@ Tk. . . .pe	day Tk.
	80-479 Helper (Engine boat)	0.001338	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00%Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.116400	cum	@ Tk. . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8	0.011640	cum	@ Tk. . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.008000	ltr	@ Tk. . . pe	ltr Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000270	ltr	@ Tk. . . pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	11.400000	m	@ Tk. . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001440	kg	@ Tk. . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.002000	No	@ Tk. . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.001000	day	@ Tk. . . pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000400	day	@ Tk. . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.002000	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000625	day	@ Tk. . . pe	day Tk.
	80-370 Labour, Skilled	0.062500	day	@ Tk. . . pe	day Tk.
	80-375 Labour, Unskilled	0.004163	day	@ Tk. . . pe	day Tk.
	80-477 Operator, Engine boat	0.001213	day	@ Tk. . . pe	day Tk.
	80-479 Helper (Engine boat)	0.001213	day	@ Tk. . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est 2.50%	Tk.
				Item Total	Tk.
				Contractor's Prof 10.00%	Tk.
				Total	Tk.
				VAT 7.00%	Tk.
				Item Grand Total	Tk.

A

M

✓

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.084000	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8	0.008400	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.005880	ltr	@ Tk. . . .pe	ltr Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000200	ltr	@ Tk. . . .pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	9.600000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001200	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001670	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.000738	day	@ Tk. . . .pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000288	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.001925	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000525	day	@ Tk. . . .pe	day Tk.
	80-370 Labour, Skilled	0.051663	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.004163	day	@ Tk. . . .pe	day Tk.
	80-477 Operator, Engine boat	0.000850	day	@ Tk. . . .pe	day Tk.
	80-479 Helper (Engine boat)	0.000850	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000225	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.073000	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.007300	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.005000	ltr	@ Tk. . . .pe	ltr Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000170	ltr	@ Tk. . . .pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	9.300000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001200	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001670	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.000625	day	@ Tk. . . .pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000250	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.001750	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000525	day	@ Tk. . . .pe	day Tk.
	80-370 Labour, Skilled	0.044088	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.003125	day	@ Tk. . . .pe	day Tk.
	80-477 Operator, Engine boat	0.000750	day	@ Tk. . . .pe	day Tk.
	80-479 Helper (Engine boat)	0.000750	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est 2.50%	Tk.
				Item Total	Tk.
				Contractor's Prof 10.00%	Tk.
				Total	Tk.
				VAT 7.00%	Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.052000	cum	@ Tk. . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.005200	cum	@ Tk. . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.004000	ltr	@ Tk. . . pe	ltr Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000130	ltr	@ Tk. . . pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	7.800000	m	@ Tk. . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001000	kg	@ Tk. . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001000	No	@ Tk. . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.000500	day	@ Tk. . . pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000175	day	@ Tk. . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.001500	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000500	day	@ Tk. . . pe	day Tk.
	80-370 Labour, Skilled	0.039625	day	@ Tk. . . pe	day Tk.
	80-375 Labour, Unskilled	0.003125	day	@ Tk. . . pe	day Tk.
	80-477 Operator, Engine boat	0.000538	day	@ Tk. . . pe	day Tk.
	80-479 Helper (Engine boat)	0.000538	day	@ Tk. . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00%Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency				
	Work: 250 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.166400	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.016640	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.011760	ltr	@ Tk. . . .pe	ltr Tk.
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	2.625000	sqm	@ Tk. . . .pe	sqm Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000390	ltr	@ Tk. . . .pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	27.000000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001690	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.002350	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.001475	day	@ Tk. . . .pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000550	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.007088	day	@ Tk. . . .pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002775	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000625	day	@ Tk. . . .pe	day Tk.
	80-370 Labour, Skilled	0.075000	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.005000	day	@ Tk. . . .pe	day Tk.
	80-477 Operator, Engine boat	0.001663	day	@ Tk. . . .pe	day Tk.
	80-479 Helper (Engine boat)	0.001663	day	@ Tk. . . .pe	day Tk.
	80-495 Operator, Sewing Machine	0.005000	day	@ Tk. . . .pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002500	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.133300	cum	@ Tk. . . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8	0.013330	cum	@ Tk. . . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.009100	ltr	@ Tk. . . . pe	ltr Tk.
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	2.173500	sqm	@ Tk. . . . pe	sqm Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000300	ltr	@ Tk. . . . pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	25.200000	m	@ Tk. . . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001500	kg	@ Tk. . . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.002100	No	@ Tk. . . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.001125	day	@ Tk. . . . pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000450	day	@ Tk. . . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.007013	day	@ Tk. . . . pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002775	day	@ Tk. . . . pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000625	day	@ Tk. . . . pe	day Tk.
	80-370 Labour, Skilled	0.068000	day	@ Tk. . . . pe	day Tk.
	80-375 Labour, Unskilled	0.004550	day	@ Tk. . . . pe	day Tk.
	80-477 Operator, Engine boat	0.001338	day	@ Tk. . . . pe	day Tk.
	80-479 Helper (Engine boat)	0.001338	day	@ Tk. . . . pe	day Tk.
	80-495 Operator, Sewing Machine	0.005000	day	@ Tk. . . . pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002500	day	@ Tk. . . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00%Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

AS

Baba

✓

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.116400	cum	@ Tk. . . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.011640	cum	@ Tk. . . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.008000	ltr	@ Tk. . . . pe	ltr Tk.
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	2.126250	sqm	@ Tk. . . . pe	sqm Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000270	ltr	@ Tk. . . . pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-540 Polypropylenc/nylon thread	24.900000	m	@ Tk. . . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001440	kg	@ Tk. . . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.002000	No	@ Tk. . . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.001000	day	@ Tk. . . . pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000400	day	@ Tk. . . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.007000	day	@ Tk. . . . pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002775	day	@ Tk. . . . pc	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000625	day	@ Tk. . . . pe	day Tk.
	80-370 Labour, Skilled	0.062500	day	@ Tk. . . . pe	day Tk.
	80-375 Labour, Unskilled	0.004163	day	@ Tk. . . . pe	day Tk.
	80-477 Operator, Engine boat	0.001213	day	@ Tk. . . . pe	day Tk.
	80-479 Helper (Engine boat)	0.001213	day	@ Tk. . . . pe	day Tk.
	80-495 Operator, Sewing Machine	0.005000	day	@ Tk. . . . pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002500	day	@ Tk. . . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est 2.50%	Tk.
				Item Total	Tk.
				Contractor's Prof 10.00%	Tk.
				Total	Tk.
				VAT 7.00%	Tk.
				Item Grand Total	Tk.





ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.084000	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.008400	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.005880	ltr	@ Tk. . . .pe	ltr Tk.
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	1.680000	sqm	@ Tk. . . .pe	sqm Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000200	ltr	@ Tk. . . .pe	ltr Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	21.600000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001200	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001670	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.000738	day	@ Tk. . . .pe	day Tk.
	70-074 Generator.....8hrs ...per day	0.000288	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.006088	day	@ Tk. . . .pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002500	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000525	day	@ Tk. . . .pe	day Tk.
	80-370 Labour, Skilled	0.051663	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.004163	day	@ Tk. . . .pe	day Tk.
	80-477 Operator, Engine boat	0.000850	day	@ Tk. . . .pe	day Tk.
	80-479 Helper (Engine boat)	0.000850	day	@ Tk. . . .pe	day Tk.
	80-495 Operator, Sewing Machine	0.004163	day	@ Tk. . . .pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002088	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000225	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency				
	Work: 110 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.073000	cum	@ Tk. . . .pe	Tk.
	10-365 (Sand, FM >= 0.8	0.007300	cum	@ Tk. . . .pe	Tk. (Misc. Sundry)
	Sub Total				Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.005000	ltr	@ Tk. . . .pe	Tk.
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	1.496250	sqm	@ Tk. . . .pe	Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000170	ltr	@ Tk. . . .pe	Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	Tk.
	20-540 Polypropylene/nylon thread	20.700000	m	@ Tk. . . .pe 100	Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001200	kg	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001670	No	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.000625	day	@ Tk. . . .pe	Tk.
	70-074 Generator.....8hrs ...per day	0.000250	day	@ Tk. . . .pe	Tk.
	70-980 Sewing machine;8 hr day	0.005913	day	@ Tk. . . .pe	Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002500	day	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000525	day	@ Tk. . . .pe	Tk.
	80-370 Labour, Skilled	0.044088	day	@ Tk. . . .pe	Tk.
	80-375 Labour, Unskilled	0.003125	day	@ Tk. . . .pe	Tk.
	80-477 Operator, Engine boat	0.000750	day	@ Tk. . . .pe	Tk.
	80-479 Helper (Engine boat)	0.000750	day	@ Tk. . . .pe	Tk.
	80-495 Operator, Sewing Machine	0.004163	day	@ Tk. . . .pe	Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002088	day	@ Tk. . . .pe	Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
	Sum of Sub Total				Tk.
	Overhead & Est 2.50%				Tk.
	Item Total				Tk.
	Contractor's Prof 10.00%				Tk.
	Total				Tk.
	VAT 7.00%				Tk.
	Item Grand Total				Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency				
	Work: 80 kg wt.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.052000	cum	@ Tk. . . .pe	Tk.
	10-365 (Sand, FM >= 0.8	0.005200	cum	@ Tk. . . .pe	Tk. (Misc. Sundry)
	Sub Total				Tk.
20 .	<u>Materials : Misc.</u>				
	20-245 Diesel/ Fuel	0.004000	ltr	@ Tk. . . .pe	Tk.
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	1.249500	sqm	@ Tk. . . .pe	Tk.
	20-310 Lubricant (Mobile oil etc.)	0.000130	ltr	@ Tk. . . .pe	Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	Tk.
	20-540 Polypropylene/nylon thread	18.000000	m	@ Tk. . . .pe 100 m	Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001000	kg	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001000	No	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
70 .	<u>Equipment, Tools</u>				
	70-068 Flat top engine boat, 40 tonne capacity: 8 hrs d	0.000500	day	@ Tk. . . .pe	Tk.
	70-074 Generator.....8hrs ...per day	0.000175	day	@ Tk. . . .pe	Tk.
	70-980 Sewing machine;8 hr day	0.005075	day	@ Tk. . . .pe	Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002088	day	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
80 .	<u>Labour</u>				
	80-305 Head Man	0.000500	day	@ Tk. . . .pe	Tk.
	80-370 Labour, Skilled	0.039625	day	@ Tk. . . .pe	Tk.
	80-375 Labour, Unskilled	0.003125	day	@ Tk. . . .pe	Tk.
	80-477 Operator, Engine boat	0.000538	day	@ Tk. . . .pe	Tk.
	80-479 Helper (Engine boat)	0.000538	day	@ Tk. . . .pe	Tk.
	80-495 Operator, Sewing Machine	0.003575	day	@ Tk. . . .pe	Tk.
	80-780 Helper, Operator (Sewing Machine)	0.001788	day	@ Tk. . . .pe	Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	Tk.
	Sub Total				Tk.
	Sum of Sub Total				Tk.
	Overhead & Est			2.50%	Tk.
	Item Total				Tk.
	Contractor's Prof			10.00%	Tk.
	Total				Tk.
	VAT			7.00%	Tk.
	Item Grand Total				Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.166400	cum	@ Tk. . . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.016640	cum	@ Tk. . . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	12.000000	m	@ Tk. . . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001000	kg	@ Tk. . . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001000	No	@ Tk. . . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000550	day	@ Tk. . . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.002088	day	@ Tk. . . . pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.080208	day	@ Tk. . . . pe	day Tk.
	80-375 Labour, Unskilled	0.007708	day	@ Tk. . . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

10

Raj

✓

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.133300	cum	@ Tk. . . . pe cum	Tk.
	10-365 (Sand, FM >= 0.8)	0.013330	cum	@ Tk. . . . pe cum	Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . . pe ltr	Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . . pe ltr	Tk.
	20-540 Polypropylene/nylon thread	11.400000	m	@ Tk. . . . pe 100 m	Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000909	kg	@ Tk. . . . pe kg	Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000909	No	@ Tk. . . . pe No	Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000450	day	@ Tk. . . . pe day	Tk.
	70-980 Sewing machine;8 hr day	0.002013	day	@ Tk. . . . pe day	Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.075000	day	@ Tk. . . . pe day	Tk.
	80-375 Labour, Unskilled	0.007050	day	@ Tk. . . . pe day	Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . . pe day	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est 2.50%	Tk.
				Item Total	Tk.
				Contractor's Prof 10.00%	Tk.
				Total	Tk.
				VAT 7.00%	Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.116400	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.011640	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	11.400000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000833	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000833	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000400	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.002000	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.064583	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.006246	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.084000	cum	@ Tk. . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.008400	cum	@ Tk. . . pe	cum Tk. (Misc. Sundry)
	Sub Total				Tk.
20 .	<u>Materials : Misc.</u>				
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	9.600000	m	@ Tk. . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000769	kg	@ Tk. . . pe	kg Tk.
	Sub Total				Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000769	No	@ Tk. . . pe	No Tk.
	Sub Total				Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000288	day	@ Tk. . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.001925	day	@ Tk. . . pe	day Tk.
	Sub Total				Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.043854	day	@ Tk. . . pe	day Tk.
	80-375 Labour, Unskilled	0.005517	day	@ Tk. . . pe	day Tk.
	80-785 Supervisor	0.000225	day	@ Tk. . . pe	day Tk.
	Sub Total				Tk.
	Sum of Sub Total				Tk.
	Overhead & Est			2.50%	Tk.
	Item Total				Tk.
	Contractor's Prof			10.00%	Tk.
	Total				Tk.
	VAT			7.00%	Tk.
	Item Grand Total				Tk.





ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.073000	cum	@ Tk. . . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.007300	cum	@ Tk. . . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-440 Paint : terpine (terpin)	0.000909	ltr	@ Tk. . . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	9.300000	m	@ Tk. . . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000667	kg	@ Tk. . . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000667	No	@ Tk. . . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000250	day	@ Tk. . . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.001750	day	@ Tk. . . . pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.039625	day	@ Tk. . . . pe	day Tk.
	80-375 Labour, Unskilled	0.004375	day	@ Tk. . . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.





ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.052000	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.005200	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	7.800000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000556	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000556	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000175	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.001500	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.034417	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.004167	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.166400	cum	@ Tk. . . pe	Tk.
	10-365 (Sand, FM >= 0.8)	0.016640	cum	@ Tk. . . pe	Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	2.625000	sqm	@ Tk. . . pe	Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . pe	Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . pe	Tk.
	20-540 Polypropylene/nylon thread	27.000000	m	@ Tk. . . pe 100	Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.001000	kg	@ Tk. . . pe	Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.001000	No	@ Tk. . . pe	Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000550	day	@ Tk. . . pe	Tk.
	70-980 Sewing machine;8 hr day	0.007088	day	@ Tk. . . pe	Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002775	day	@ Tk. . . pe	Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.080208	day	@ Tk. . . pe	Tk.
	80-375 Labour, Unskilled	0.007708	day	@ Tk. . . pe	Tk.
	80-495 Operator, Sewing Machine	0.005000	day	@ Tk. . . pe	Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002500	day	@ Tk. . . pe	Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . pe	Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est 2.50%	Tk.
				Item Total	Tk.
				Contractor's Prof 10.00%	Tk.
				Total	Tk.
				VAT 7.00%	Tk.
				Item Grand Total	Tk.





ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.133300	cum	@ Tk. . . pe	Tk. cum
	10-365 (Sand, FM >= 0.8)	0.013330	cum	@ Tk. . . pe	Tk. (Misc. Sundry) cum
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	2.173500	sqm	@ Tk. . . pe	Tk. sqm
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . pe	Tk. ltr
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . pe	Tk. ltr
	20-540 Polypropylene/nylon thread	25.200000	m	@ Tk. . . pe	Tk. 100 m
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000909	kg	@ Tk. . . pe	Tk. kg
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000909	No	@ Tk. . . pe	Tk. No
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000450	day	@ Tk. . . pe	Tk. day
	70-980 Sewing machine;8 hr day	0.007013	day	@ Tk. . . pe	Tk. day
	70-990 Cutter (geo-textile);8 hr day	0.002775	day	@ Tk. . . pe	Tk. day
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.075000	day	@ Tk. . . pe	Tk. day
	80-375 Labour, Unskilled	0.007050	day	@ Tk. . . pe	Tk. day
	80-495 Operator, Sewing Machine	0.005000	day	@ Tk. . . pe	Tk. day
	80-780 Helper, Operator (Sewing Machine)	0.002500	day	@ Tk. . . pe	Tk. day
	80-785 Supervisor	0.000250	day	@ Tk. . . pe	Tk. day
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00% Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.





ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.116400	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.011640	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
	Sub Total				Tk.
20 .	<u>Materials : Misc.</u>				
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	2.126250	sqm	@ Tk. . . .pe	sqm Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	24.900000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000833	kg	@ Tk. . . .pe	kg Tk.
	Sub Total				Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000833	No	@ Tk. . . .pe	No Tk.
	Sub Total				Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000400	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.007000	day	@ Tk. . . .pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002775	day	@ Tk. . . .pe	day Tk.
	Sub Total				Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.064583	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.006246	day	@ Tk. . . .pe	day Tk.
	80-495 Operator, Sewing Machine	0.005000	day	@ Tk. . . .pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002500	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	day Tk.
	Sub Total				Tk.
	Sum of Sub Total				Tk.
	Overhead & Est			2.50%	Tk.
	Item Total				Tk.
	Contractor's Prof			10.00%	Tk.
	Total				Tk.
	VAT			7.00%	Tk.
	Item Grand Total				Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.084000	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.008400	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	1.680000	sqm	@ Tk. . . .pe	sqm Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	21.600000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000769	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000769	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000288	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.006088	day	@ Tk. . . .pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002500	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.043854	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.005517	day	@ Tk. . . .pe	day Tk.
	80-495 Operator, Sewing Machine	0.004163	day	@ Tk. . . .pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002088	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000225	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00%Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.073000	cum	@ Tk. . . pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.007300	cum	@ Tk. . . pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	1.496250	sqm	@ Tk. . . pe	sqm Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . pe	ltr Tk.
	20-540 Polypropylene/nylon thread	20.700000	m	@ Tk. . . pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000667	kg	@ Tk. . . pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000667	No	@ Tk. . . pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000250	day	@ Tk. . . pe	day Tk.
	70-980 Sewing machine;8 hr day	0.005913	day	@ Tk. . . pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002500	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.039625	day	@ Tk. . . pe	day Tk.
	80-375 Labour, Unskilled	0.004375	day	@ Tk. . . pe	day Tk.
	80-495 Operator, Sewing Machine	0.004163	day	@ Tk. . . pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.002088	day	@ Tk. . . pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00%Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

⑩

M

✓

ANALYSIS TEMPLATE REPORT

Primary Element	Secondary Element	Weight	Unit	Element Rate	Value
40 . Protective Work					
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work				
10 .	<u>Materials : Concrete</u>				
	10-365 Sand, FM >= 0.8	0.052000	cum	@ Tk. . . .pe	cum Tk.
	10-365 (Sand, FM >= 0.8)	0.005200	cum	@ Tk. . . .pe	cum Tk. (Misc. Sundry)
				Sub Total	Tk.
20 .	<u>Materials : Misc.</u>				
	20-277 Geo-tex filter (Polystar): thick>=3.0mm;mass>	1.249500	sqm	@ Tk. . . .pe	sqm Tk.
	20-435 Paint : Synthetic Enamel	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-440 Paint : terpentine (terpin)	0.000909	ltr	@ Tk. . . .pe	ltr Tk.
	20-540 Polypropylene/nylon thread	18.000000	m	@ Tk. . . .pe	100 m Tk.
	20-550 Rope, nylon: 10 mm dia, 64 gm/m	0.000556	kg	@ Tk. . . .pe	kg Tk.
				Sub Total	Tk.
30 .	<u>Wood Work</u>				
	30-003 Bamboo piece: 2m long, 50 mm dia	0.000556	No	@ Tk. . . .pe	No Tk.
				Sub Total	Tk.
70 .	<u>Equipment, Tools</u>				
	70-074 Generator.....8hrs ...per day	0.000175	day	@ Tk. . . .pe	day Tk.
	70-980 Sewing machine;8 hr day	0.005075	day	@ Tk. . . .pe	day Tk.
	70-990 Cutter (geo-textile);8 hr day	0.002088	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
80 .	<u>Labour</u>				
	80-370 Labour, Skilled	0.034417	day	@ Tk. . . .pe	day Tk.
	80-375 Labour, Unskilled	0.004167	day	@ Tk. . . .pe	day Tk.
	80-495 Operator, Sewing Machine	0.003575	day	@ Tk. . . .pe	day Tk.
	80-780 Helper, Operator (Sewing Machine)	0.001788	day	@ Tk. . . .pe	day Tk.
	80-785 Supervisor	0.000250	day	@ Tk. . . .pe	day Tk.
				Sub Total	Tk.
				Sum of Sub Total	Tk.
				Overhead & Est	2.50% Tk.
				Item Total	Tk.
				Contractor's Prof	10.00%Tk.
				Total	Tk.
				VAT	7.00% Tk.
				Item Grand Total	Tk.

১১/১৩-৬

Printed: March 13, 2019

ITEM RATES For Barisal O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	170.82
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	143.30
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	128.39
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	98.85
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	85.63
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	68.17

(H)

Amber

✓

ITEM RATES For Barisal O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		439.60
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		368.07
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		348.49
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		273.75
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		242.58
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		199.66





Printed: March 13, 2019

ITEM RATES For Barisal O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	164.07
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	140.16
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	122.68
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	88.34
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	78.06
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	61.10
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	432.85
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	364.93
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	342.78
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	263.25
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	235.01
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	192.59



Printed: March 13, 2019

ITEM RATES For Bhola O & M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59

@

Myka

✓

Printed: March 13, 2019

ITEM RATES For Bhola O & M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08



ITEM RATES For Bhola O & M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15

Printed: March 13, 2019

ITEM RATES For Bogra O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	154.61
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	130.00
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	116.66
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	90.09
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	78.07
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	62.45







Printed: March 13, 2019

ITEM RATES For Bogra O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		423.39
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		354.78
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		336.76
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		265.00
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		235.03
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		193.94

(10)

[Signature]

[Signature]

ITEM RATES For Bogra O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	147.54
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	126.49
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	110.77
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	79.80
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	70.60
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	55.52
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	416.33
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	351.26
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	330.88
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	254.71
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	227.56
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	187.00





Printed: March 13, 2019

ITEM RATES For Chandpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	159.03
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	133.54
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	119.75
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	92.32
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	80.01
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	63.83

(A)

[Signature]

[Signature]

ITEM RATES For Chandpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		427.81
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		358.31
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		339.85
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		267.22
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		236.96
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		195.32





Printed: March 13, 2019

ITEM RATES For Chandpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	151.96
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	130.03
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	113.86
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	82.03
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	72.54
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	56.90
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	420.74
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	354.80
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	333.96
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	256.94
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	229.49
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	188.38

(R)

Arba

✓

ITEM RATES For Chittagong O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	170.79
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	143.26
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	128.36
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	98.79
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	85.60
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	68.14





Printed: March 13, 2019

ITEM RATES For Chittagong O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		439.81
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		368.28
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		348.70
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		273.90
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		242.75
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		199.80

(R)

[Signature]

[Signature]

ITEM RATES For Chittagong O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	163.87
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	139.98
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	122.52
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	88.20
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	77.95
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	61.00
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	432.90
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	365.00
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	342.87
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	263.31
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	235.11
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	192.66





ITEM RATES For Comilla O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59



ITEM RATES For Comilla O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08

(K)

Rajda

m

ITEM RATES For Comilla O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15

⑩

Rajon

✓

J

Printed: March 13, 2019

ITEM RATES For Cox's Bazar WD Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	170.79
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	143.26
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	128.36
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	98.79
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	85.60
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	68.14

(10)

[Signature]

[Signature]

ITEM RATES For Cox's Bazar WD Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		439.81
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		368.28
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		348.70
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		273.90
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		242.75
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		199.80

②

Mha

N

ITEM RATES For Cox's Bazar WD Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	163.87
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	139.98
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	122.52
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	88.20
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	77.95
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	61.00
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	432.90
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	365.00
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	342.87
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	263.31
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	235.11
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	192.66





Printed: March 13, 2019

ITEM RATES For Dhaka O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	173.04
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	145.07
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	129.94
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	99.94
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	86.59
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	68.85

(10)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Dhaka O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		442.06
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		370.08
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		350.29
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		275.05
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		243.75
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		200.51

(10)

By/for

✓

Printed: March 13, 2019

ITEM RATES For Dhaka O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	166.10
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	141.77
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	124.08
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	89.33
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	78.93
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	61.70
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	435.12
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	366.78
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	344.43
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	264.44
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	236.09
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	193.36

(4)

Dhaka

✓

Printed: March 13, 2019

ITEM RATES For Feni O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	170.07
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	142.39
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	127.47
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	97.89
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	84.85
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	67.28

②

[Signature]

✓

Printed: March 13, 2019

ITEM RATES For Feni O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		438.85
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		367.16
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		347.58
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		272.80
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		241.81
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.77

(10)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Feni O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	163.00
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	138.87
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	121.58
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	87.60
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	77.38
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	60.35
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	431.78
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	363.65
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	341.69
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	262.51
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	234.34
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.84

(K)

By

✓

Printed: March 13, 2019

ITEM RATES For Faridpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59

(10)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Faridpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08

(A)

[Signature]

✓

Printed: March 13, 2019

ITEM RATES For Faridpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15

(8)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Jessore O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59

(10)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Jessore O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08

AS

Baba

✓

ITEM RATES For Jessore O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15

②

Baka

✓

ITEM RATES For Khulna O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59





ITEM RATES For Khulna O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08



ITEM RATES For Khulna O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15





ITEM RATES For Kushtia O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59





ITEM RATES For Kushtia O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08





ITEM RATES For Kushtia O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15





ITEM RATES For Moulvibazar O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59





ITEM RATES For Moulvibazar O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08





ITEM RATES For Moulvibazar O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15





ITEM RATES For Mymensingh O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	170.07
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	142.39
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	127.47
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	97.89
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	84.85
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	67.28

ITEM RATES For Mymensingh O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		438.85
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		367.16
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		347.58
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		272.80
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		241.81
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.77



ITEM RATES For Mymensingh O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	163.00
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	138.87
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	121.58
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	87.60
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	77.38
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	60.35
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	431.78
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	363.65
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	341.69
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	262.51
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	234.34
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.84





ITEM RATES For Pabna O & M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59





Printed: March 13, 2019

ITEM RATES For Pabna O & M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08

(A)

[Signature]

[Signature]

ITEM RATES For Pabna O & M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15





Printed: March 13, 2019

ITEM RATES For Patuakhali WD Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	167.86
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	140.62
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	125.93
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	96.78
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	83.88
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	66.59

(10)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Patuakhali WD Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		436.64
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		365.39
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		346.03
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		271.68
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		240.84
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		198.08

(M)

Baba

N

Printed: March 13, 2019

ITEM RATES For Patuakhali WD Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	160.79
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	137.10
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	120.04
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	86.49
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	76.41
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	59.66
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	429.57
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	361.88
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	340.14
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	261.39
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	233.37
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	191.15



ITEM RATES For Rajshahi O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	154.57
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	129.65
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	116.24
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	89.46
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	77.62
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	61.72





Printed: March 13, 2019

ITEM RATES For Rajshahi O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		423.35
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		354.36
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		336.26
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		264.33
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		234.51
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		193.17







Printed: March 13, 2019

ITEM RATES For Rajshahi O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	148.11
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	126.47
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	110.86
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	80.00
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	70.76
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	55.34
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	416.90
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	351.17
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	330.87
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	254.87
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	227.65
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	186.80

(A)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Sylhet O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	170.83
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	143.30
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	128.39
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	98.82
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	85.63
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	68.16

(10)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Sylhet O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		439.85
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		368.31
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		348.74
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		273.93
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		242.78
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		199.82

(10)

By/ka

✓

Printed: March 13, 2019

ITEM RATES For Sylhet O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	163.89
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	140.00
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	122.54
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	88.22
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	77.96
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	61.01
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	432.91
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	365.01
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	342.88
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	263.32
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	235.12
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	192.67

(S)

(Sylhet)

✓

Printed: March 13, 2019

ITEM RATES For Rangpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	159.03
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	133.54
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	119.75
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	92.32
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	80.01
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	63.83

(18)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Rangpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		427.81
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		358.31
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		339.85
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		267.22
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		236.96
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		195.32



Printed: March 13, 2019

ITEM RATES For Rangpur O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	151.96
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	130.03
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	113.86
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	82.03
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	72.54
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	56.90
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	420.74
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	354.80
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	333.96
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	256.94
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	229.49
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	188.38

(M)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Thakurgaon O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-489-10	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt.	no	147.99
40-489-15	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt.	no	124.70
40-489-20	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt.	no	112.03
40-489-30	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt.	no	86.74
40-489-40	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt.	no	75.16
40-489-50	Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt.	no	60.38

(10)

[Signature]

[Signature]

Printed: March 13, 2019

ITEM RATES For Thakurgaon O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-493-10	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 250 kg wt. No.		416.77
40-493-15	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 200 kg wt. No.		349.47
40-493-20	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 175 kg wt. No.		332.13
40-493-30	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 125 kg wt. No.		261.65
40-493-40	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 110 kg wt. No.		232.12
40-493-50	Supply, Filling and Dumping of Geo-bag from Engine Boat for Emergency Work: 80 kg wt. No.		191.87

(R)

Asst.

✓

ITEM RATES For Thakurgaon O&M Circle

Year : 2018-19

Item Code	Description	Unit Meas.	Rate (Taka)
40 . Protective Work			
40-495-10	Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	140.92
40-495-15	Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	121.18
40-495-20	Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work.	No.	106.14
40-495-30	Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	76.45
40-495-40	Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	67.69
40-495-50	Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	53.45
40-496-10	Supply, Filling and Placing of Geo-bag: 250 kg wt. for Emergency Work	No.	409.70
40-496-15	Supply, Filling and Placing of Geo-bag: 200 kg wt. for Emergency Work	No.	345.96
40-496-20	Supply, Filling and Placing of Geo-bag: 175 kg wt. for Emergency Work	No.	326.24
40-496-30	Supply, Filling and Placing of Geo-bag: 125 kg wt. for Emergency Work	No.	251.36
40-496-40	Supply, Filling and Placing of Geo-bag: 110 kg wt. for Emergency Work	No.	224.65
40-496-50	Supply, Filling and Placing of Geo-bag: 80 kg wt. for Emergency Work	No.	184.93



